

SWIN  
BUR  
\* NE \*


SWINBURNE  
UNIVERSITY OF  
TECHNOLOGY

# Work Breakdown Matrix



**Prof. Russell Kenley**  
Swinburne University of Technology  
Email: [rkenley@swin.edu.au](mailto:rkenley@swin.edu.au)

# Learning objectives



# Method



# Who am I?



- Professor of Management  
Swinburne University of Technology
- Visiting Professor of Construction  
Unitec New Zealand
- Director – Micro Planning International
- Designing underlying theory for LBMS and  
developing applications
- SBEnrc Program Director 2010-2015



# Introduction

## Issues

- Project decomposition is important
- WBS is a well developed method
- Its been with us now 55 years
- Is it time to revisit?
- Current methods are repetitive and hard work
- Project control remains a problem
- There is a better way

## Proposal

- Need to go back to basics
- Recognise the role of location
- Extract location from the WBS
- Use a Location-work breakdown matrix
- Redesign PM processes and software!

# Development of WBS

## History

- Designed into the US Navy Polaris Missile project in 1957
- Defined and published by 1962 in DoD Guide to PERT
- Codified into a standard in 1968 in US MIL-STD-881
- Adopted in DEF(AUST)5664 (1995) and Rev A (2004)
- Developed as a practitioner's tool for project decomposition

## What is it?

- A task-oriented family tree of activities which organises, defines and graphically displays the total work to be accomplished in order to achieve the final objectives of the project (PMI, from Chandrashekar et al. 1993)
- The WBS is the cornerstone of a project and provides the basis for technical, cost and schedule control. [DEF(AUST)5664A]










# WBS representation

## Tree structures



Level 1	Level 2	Level 3	Level 4
Project			<b>Outlining</b>
	Task 1		
		Sub Task1.1	
			Work Package 1.1.1
			Work Package 1.1.2
			Work Package 1.1.3
			Work Package 1.1.4
		Sub Task1.2	
			Work Package 1.2.1
			Work Package 1.2.2
			Work Package 1.2.3
			Work Package 1.2.4
	Task 2		
		Sub Task2.1	
			Work Package 2.1.1
			Work Package 2.1.2
			Work Package 2.1.3
			Work Package 2.1.4
		Sub Task2.2	
			Work Package 2.2.1
			Work Package 2.2.2
			Work Package 2.2.3
			Work Package 2.2.4
		Sub Task2.3	
			Work Package 2.3.1
			Work Package 2.3.2

# AUS(DEF)5664 Requirement 1

- Integrated – A single top WBS Element covers the total body of work.
  - Distinct – Every WBS Element is a distinct Product or Enabling Service, which is mutually exclusive from other Products and Enabling Services.
  - Children – Every WBS Element has either no children, or multiple children.
  - Descendant – Every child WBS Element has only one parent and is a descendant of the top WBS Element.
  - Necessary – Every child WBS Element is needed to deliver the parent.
  - Sufficient – If all child WBS Elements are complete, their parent is complete.
  - Complete – The complete scope of work is captured in the WBS.
- Rules I have issue with
  - 100% Rule (Project Scope)
  - Every WBS Element has either no children, or multiple children.

# Can we fix it?






# Can we fix it? Yes we can!



# Relationship to other decomposition structures



- Organisational Breakdown Structure (OBS)
- Bill of Materials (BOM)
- Resource Breakdown Structure (RBS)
- None of these change the demands on the WBS


# Multi-dimensional decomposition relationships

## NASA



NASA WBS Handbook (2010)

## Moine's 3DWBS



Moine (2012)



# Infrastructure project decomposition

## Vertical Infrastructure




## Horizontal Infrastructure



# Infrastructure project decomposition

## Distributed Infrastructure Assets



## Distributed Construction/Maintenance











# Location-based management systems


- Managing by location in construction improves production














# Location-based management systems





## Analog



## Digital







# Location effects on project decomposition

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
  - BO1.4 .3 .1 .A . 1 Column
    - BO1.4 .3 .1 .A . 1.1 Rebar
    - BO1.4 .3 .1 .A . 1.2 Form Work
    - BO1.4 .3 .1 .A . 1.3 Concreting
  - BO1.4 .3 .1 .A . 2 Shear Wall
    - BO1.4 .3 .1 .A . 2 .1 Rebar
    - BO1.4 .3 .1 .A . 2 .2 Form Work
    - BO1.4 .3 .1 .A . 2 .3 Concreting
  - BO1.4 .3 .1 .A . 3 Slab
    - BO1.4 .3 .1 .A . 3 .1 Form Work
    - BO1.4 .3 .1 .A . 3 .2 Rebar
    - BO1.4 .3 .1 .A . 3 .3 MEP Work
    - BO1.4 .3 .1 .A . 3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
- BO1.4 .3 .2 .A Slab Work
  - BO1.4 .3 .2 .A . 1 Column
    - BO1.4 .3 .2 .A . 1 .1 Rebar
    - BO1.4 .3 .2 .A . 1 .2 Form Work
    - BO1.4 .3 .2 .A . 1 .3 Concreting
  - BO1.4 .3 .2 .A . 2 Shear Wall
    - BO1.4 .3 .2 .A . 2 .1 Rebar
    - BO1.4 .3 .2 .A . 2 .2 Form Work
    - BO1.4 .3 .2 .A . 2 .3 Concreting
  - BO1.4 .3 .2 .A . 3 Slab
    - BO1.4 .3 .2 .A . 3 .1 Form Work
    - BO1.4 .3 .2 .A . 3 .2 Rebar
    - BO1.4 .3 .2 .A . 3 .3 MEP Work
    - BO1.4 .3 .2 .A . 3 .4 Concreting
- BO1.4 .3 .3 Second Floor Level
- BO1.4 .3 .3 .A Slab Work
  - BO1.4 .3 .3 .A . 1 Column
    - BO1.4 .3 .3 .A . 2 Shear Wall
    - BO1.4 .3 .3 .A . 3 Slab
  - BO1.4 .3 .3 .B Part 2
    - BO1.4 .3 .3 .B . 1 Column
    - BO1.4 .3 .3 .B . 2 Shear Wall
    - BO1.4 .3 .3 .B . 3 Slab
- BO1.4 .3 .4 Third Floor Level
- BO1.4 .3 .4 .A Part 1
  - BO1.4 .3 .4 .A . 1 Column
  - BO1.4 .3 .4 .A . 2 Shear Wall
  - BO1.4 .3 .4 .A . 3 Slab
- BO1.4 .3 .4 .B Part 2
  - BO1.4 .3 .4 .B . 1 Column
  - BO1.4 .3 .4 .B . 2 Shear Wall
  - BO1.4 .3 .4 .B . 3 Slab

- Location has been found to be a key breakdown component of traditional WBS (Ibrahim et al., 2009)
- Integrating ‘location’ into [traditional] WBS decomposition necessitates substantial repetition in data and processes (Stal-Le Cardinal & Marle, 2006)



# Location-Work Breakdown Matrix

- **BO1 RESI. BLDG.PROJECT**
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- **BO1.4 .3 .1 Ground Floor Level**
- BO1.4 .3 .1 .A Slab Work
  - BO1.4 .3 .1 .A .1 Column
    - BO1.4 .3 .1 .A .1.1 Rebar
    - BO1.4 .3 .1 .A .1.2 Form Work
    - BO1.4 .3 .1 .A .1.3 Concreting
  - BO1.4 .3 .1 .A .2 Shear Wall
    - BO1.4 .3 .1 .A .2.1 Rebar
    - BO1.4 .3 .1 .A .2.2 Form Work
    - BO1.4 .3 .1 .A .2.3 Concreting
  - BO1.4 .3 .1 .A .3 Slab
    - BO1.4 .3 .1 .A .3.1 Form Work
    - BO1.4 .3 .1 .A .3.2 Rebar
    - BO1.4 .3 .1 .A .3.3 MEP Work
    - BO1.4 .3 .1 .A .3.4 Concreting
- **BO1.4 .3 .2 First Floor Level**
- BO1.4 .3 .2 .A Slab Work
  - BO1.4 .3 .2 .A .1 Column
    - BO1.4 .3 .2 .A .1.1 Rebar
    - BO1.4 .3 .2 .A .1.2 Form Work
    - BO1.4 .3 .2 .A .1.3 Concreting
  - BO1.4 .3 .2 .A .2 Shear Wall
    - BO1.4 .3 .2 .A .2.1 Rebar
    - BO1.4 .3 .2 .A .2.2 Form Work
    - BO1.4 .3 .2 .A .2.3 Concreting
- BO1.4 .3 .2 .A .3 Slab
  - BO1.4 .3 .2 .A .3.1 Form Work
  - BO1.4 .3 .2 .A .3.2 Rebar
  - BO1.4 .3 .2 .A .3.3 MEP Work
  - BO1.4 .3 .2 .A .3.4 Concreting
- **BO1.4 .3 .3 Second Floor Level**
- BO1.4 .3 .3 .A Slab Work
  - BO1.4 .3 .3 .A .1 Column
    - BO1.4 .3 .3 .A .1.1 Rebar
    - BO1.4 .3 .3 .A .1.2 Form Work
    - BO1.4 .3 .3 .A .1.3 Concreting
  - BO1.4 .3 .3 .A .2 Shear Wall
    - BO1.4 .3 .3 .A .2.1 Rebar
    - BO1.4 .3 .3 .A .2.2 Form Work
    - BO1.4 .3 .3 .A .2.3 Concreting
  - BO1.4 .3 .3 .A .3 Slab
    - BO1.4 .3 .3 .A .3.1 Form Work
    - BO1.4 .3 .3 .A .3.2 Rebar
    - BO1.4 .3 .3 .A .3.3 MEP Work
    - BO1.4 .3 .3 .A .3.4 Concreting
- BO1.4 .3 .3 .B Part 2
  - BO1.4 .3 .3 .B .1 Column
    - BO1.4 .3 .3 .B .1.1 Rebar
    - BO1.4 .3 .3 .B .1.2 Form Work
    - BO1.4 .3 .3 .B .1.3 Concreting
  - BO1.4 .3 .3 .B .2 Shear Wall
    - BO1.4 .3 .3 .B .2.1 Rebar
    - BO1.4 .3 .3 .B .2.2 Form Work
    - BO1.4 .3 .3 .B .2.3 Concreting
  - BO1.4 .3 .3 .B .3 Slab
    - BO1.4 .3 .3 .B .3.1 Form Work
    - BO1.4 .3 .3 .B .3.2 Rebar
    - BO1.4 .3 .3 .B .3.3 MEP Work
    - BO1.4 .3 .3 .B .3.4 Concreting
- **BO1.4 .3 .4 Third Floor Level**
- BO1.4 .3 .4 .A Part 1
  - BO1.4 .3 .4 .A .1 Column
    - BO1.4 .3 .4 .A .1.1 Rebar
    - BO1.4 .3 .4 .A .1.2 Form Work
    - BO1.4 .3 .4 .A .1.3 Concreting
  - BO1.4 .3 .4 .A .2 Shear Wall
    - BO1.4 .3 .4 .A .2.1 Rebar
    - BO1.4 .3 .4 .A .2.2 Form Work
    - BO1.4 .3 .4 .A .2.3 Concreting
  - BO1.4 .3 .4 .A .3 Slab
    - BO1.4 .3 .4 .A .3.1 Form Work
    - BO1.4 .3 .4 .A .3.2 Rebar
    - BO1.4 .3 .4 .A .3.3 MEP Work
    - BO1.4 .3 .4 .A .3.4 Concreting
- BO1.4 .3 .4 .B Part 2
  - BO1.4 .3 .4 .B .1 Column
    - BO1.4 .3 .4 .B .1.1 Rebar
    - BO1.4 .3 .4 .B .1.2 Form Work
    - BO1.4 .3 .4 .B .1.3 Concreting
  - BO1.4 .3 .4 .B .2 Shear Wall
    - BO1.4 .3 .4 .B .2.1 Rebar
    - BO1.4 .3 .4 .B .2.2 Form Work
    - BO1.4 .3 .4 .B .2.3 Concreting
  - BO1.4 .3 .4 .B .3 Slab
    - BO1.4 .3 .4 .B .3.1 Form Work
    - BO1.4 .3 .4 .B .3.2 Rebar
    - BO1.4 .3 .4 .B .3.3 MEP Work
    - BO1.4 .3 .4 .B .3.4 Concreting

The used coding may be mapped as follows:

L1 .X1 .X2 .L2 .L3/X3 .X4 .T

Where:

- |                           |                                |
|---------------------------|--------------------------------|
| <b>L1=Building</b>        | – coded B01                    |
| <b>X1=Construction</b>    | – coded 4                      |
| <b>X2= Superstructure</b> | – coded 3                      |
| <b>L2=Level</b>           | – coded 1 to 3                 |
| <b>L3=Zone</b>            | – coded A to B                 |
| <b>X3=Element</b>         | – <b>not coded</b> , described |
| <b>X4=Component</b>       | – coded 1 to 3                 |
| <b>T=Activity</b>         | – coded 1 to 4                 |

The merging of L3 and X3 into a single code greatly increases confusion in interpreting this structure.

# Location-Work Breakdown Matrix

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
  - BO1.4 .3 .1 .A . 1 Column
    - BO1.4 .3 .1 .A . 1.1 Rebar
    - BO1.4 .3 .1 .A . 1.2 Form Work
    - BO1.4 .3 .1 .A . 1.3 Concreting
  - BO1.4 .3 .1 .A . 2 Shear Wall
    - BO1.4 .3 .1 .A .2 .1 Rebar
    - BO1.4 .3 .1 .A .2 .2 Form Work
    - BO1.4 .3 .1 .A .2 .3 Concreting
  - BO1.4 .3 .1 .A .3 Slab
    - BO1.4 .3 .1 .A .3 .1 Form Work
    - BO1.4 .3 .1 .A .3 .2 Rebar
    - BO1.4 .3 .1 .A .3 .3 MEP Work
    - BO1.4 .3 .1 .A .3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
- BO1.4 .3 .2 .A Slab Work
  - BO1.4 .3 .2 .A .1 Column
    - BO1.4 .3 .2 .A .1 .1 Rebar
    - BO1.4 .3 .2 .A .1 .2 Form Work
    - BO1.4 .3 .2 .A .1 .3 Concreting
  - BO1.4 .3 .2 .A .2 Shear Wall
    - BO1.4 .3 .2 .A .2 .1 Rebar
    - BO1.4 .3 .2 .A .2 .2 Form Work
    - BO1.4 .3 .2 .A .2 .3 Concreting
- BO1.4 .3 .2 .A .3 Slab
  - BO1.4 .3 .2 .A .3 .1 Form Work
  - BO1.4 .3 .2 .A .3 .2 Rebar
  - BO1.4 .3 .2 .A .3 .3 MEP Work
  - BO1.4 .3 .2 .A .3 .4 Concreting

The result will be a two lists:

- LBS: the location breakdown (the where [L])  
in this case: L1 .L2 .L3
- WBS: the work breakdown (the what [X] and how [T])  
in this case: X1 .X2 .X3 .X4 .X5 .T

With the actual work (.T) belonging at the intersection of the two lists **and thus belonging to both** which is why it requires the matrix to describe all work.

# Location effects on project decomposition

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
- BO1.4 .3 .1 .A . 1 Column
- BO1.4 .3 .1 .A . 1.1 Rebar
- BO1.4 .3 .1 .A . 1.2 Form Work
- BO1.4 .3 .1 .A . 1.3 Concreting
- BO1.4 .3 .1 .A .2 Shear Wall
- BO1.4 .3 .1 .A .2 .1 Rebar
- BO1.4 .3 .1 .A .2 .2 Form Work
- BO1.4 .3 .1 .A .2 .3 Concreting
- BO1.4 .3 .1 .A .3 Slab
- BO1.4 .3 .1 .A .3 .1 Form Work
- BO1.4 .3 .1 .A .3 .2 Rebar
- BO1.4 .3 .1 .A .3 .3 MEP Work
- BO1.4 .3 .1 .A .3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
- BO1.4 .3 .2 .A Slab Work
- BO1.4 .3 .2 .A .1 Column
- BO1.4 .3 .2 .A .1 .1 Rebar
- BO1.4 .3 .2 .A .1 .2 Form Work
- BO1.4 .3 .2 .A .1 .3 Concreting
- BO1.4 .3 .2 .A .2 Shear Wall
- BO1.4 .3 .2 .A .2 .1 Rebar
- BO1.4 .3 .2 .A .2 .2 Form Work
- BO1.4 .3 .2 .A .2 .3 Concreting

- BO1.4 .3 .2 .A .3 Slab
- BO1.4 .3 .2 .A .3 .1 Form Work
- BO1.4 .3 .2 .A .3 .2 Rebar
- BO1.4 .3 .2 .A .3 .3 MEP Work
- BO1.4 .3 .2 .A .3 .4 Concreting
- BO1.4 .3 .3 Second Floor Level
- BO1.4 .3 .3 .A Slab Work
- BO1.4 .3 .3 .A .1 Column
- BO1.4 .3 .3 .A .2 Shear Wall
- BO1.4 .3 .3 .A .3 Slab
- BO1.4 .3 .3 .B Part 2
- BO1.4 .3 .3 .B .1 Column
- BO1.4 .3 .3 .B .2 Shear Wall
- BO1.4 .3 .3 .B .3 Slab
- BO1.4 .3 .4 Third Floor Level
- BO1.4 .3 .4 .A Part 1
- BO1.4 .3 .4 .A .1 Column
- BO1.4 .3 .4 .A .2 Shear Wall
- BO1.4 .3 .4 .A .3 Slab
- BO1.4 .3 .4 .B Part 2
- BO1.4 .3 .4 .B .1 Column
- BO1.4 .3 .4 .B .2 Shear Wall
- BO1.4 .3 .4 .B .3 Slab

## LBS (L1 .L2 .L3)



- BO1 RESI. BLDG.PROJECT
- BO1.1 Ground Floor Level
- BO1.1.A Zone A
- BO1.2 First Floor Level
- BO1.2.A Zone A
- BO1.3 Second Floor Level
- BO1.3.A Zone A
- BO1.3.B Zone B
- BO1.4 Third Floor Level
- BO1.4.A Zone A
- BO1.4.B Zone B

## WBS (X1 .X2 .X3 .X4 .X5 .T)

- 4 CONSTRUCTION
- 4 .3 Super Structure
- 4 .3 .1 Slab Work
- 4 .3 .1 .1 Column
- 4 .3 .1 .1.1 Column Rebar
- 4 .3 .1 .1.2 Column Form Work
- 4 .3 .1 .1.3 Column Concreting
- 4 .3 .1 .2 Shear Wall
- 4 .3 .1 .2 .1 S'Wall Rebar
- 4 .3 .1 .2 .2 S'Wall Form Work
- 4 .3 .1 .2 .3 S'Wall Concreting
- 4 .3 .1 .3 Slab
- 4 .3 .1 .3 .1 Slab Form Work
- 4 .3 .1 .3 .2 Slab Rebar
- 4 .3 .1 .3 .3 Slab MEP Work
- 4 .3 .1 .3 .4 Slab Concreting



# Location-Work Breakdown Matrix



# Location-Work Breakdown Matrix

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
  - BO1.4 .3 .1 .A . 1 Column
  - BO1.4 .3 .1 .A . 1.1 Rebar
  - BO1.4 .3 .1 .A . 1.2 Form Work
  - BO1.4 .3 .1 .A . 1.3 Concreting
  - BO1.4 .3 .1 .A .2 Shear Wall
  - BO1.4 .3 .1 .A .2 .1 Rebar
  - BO1.4 .3 .1 .A .2 .2 Form Work
  - BO1.4 .3 .1 .A .2 .3 Concreting
  - BO1.4 .3 .1 .A .3 Slab
    - BO1.4 .3 .1 .A .3 .1 Form Work
    - BO1.4 .3 .1 .A .3 .2 Rebar
    - BO1.4 .3 .1 .A .3 .3 MEP Work
    - BO1.4 .3 .1 .A .3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
  - BO1.4 .3 .2 .A Slab Work
    - BO1.4 .3 .2 .A .1 Column
    - BO1.4 .3 .2 .A .1 .1 Rebar
    - BO1.4 .3 .2 .A .1 .2 Form Work
    - BO1.4 .3 .2 .A .1 .3 Concreting
    - BO1.4 .3 .2 .A .2 Shear Wall
    - BO1.4 .3 .2 .A .2 .1 Rebar
    - BO1.4 .3 .2 .A .2 .2 Form Work
    - BO1.4 .3 .2 .A .2 .3 Concreting
- BO1.4 .3 .2 .A .3 Slab
  - BO1.4 .3 .2 .A .3 .1 Form Work
  - BO1.4 .3 .2 .A .3 .2 Rebar
  - BO1.4 .3 .2 .A .3 .3 MEP Work
  - BO1.4 .3 .2 .A .3 .4 Concreting
- BO1.4 .3 .3 Second Floor Level
  - BO1.4 .3 .3 .A Slab Work
    - BO1.4 .3 .3 .A .1 Column
    - BO1.4 .3 .3 .A .2 Shear Wall
    - BO1.4 .3 .3 .A .3 Slab
      - BO1.4 .3 .3 .B Part 2
      - BO1.4 .3 .3 .B .1 Column
      - BO1.4 .3 .3 .B .2 Shear Wall
      - BO1.4 .3 .3 .B .3 Slab
- BO1.4 .3 .4 Third Floor Level
  - BO1.4 .3 .4 .A Part 1
    - BO1.4 .3 .4 .A .1 Column
    - BO1.4 .3 .4 .A .2 Shear Wall
    - BO1.4 .3 .4 .A .3 Slab
  - BO1.4 .3 .4 .B Part 2
    - BO1.4 .3 .4 .B .1 Column
    - BO1.4 .3 .4 .B .2 Shear Wall
    - BO1.4 .3 .4 .B .3 Slab

## Work-Location Breakdown Matrix

### Work Breakdown Structure

- 4 CONSTRUCTION
  - 4 .3 Super Structure
    - 4 .3 .1 Slab Work
      - 4 .3 .1 .1 Column
        - 4 .3 .1 .1.1 Column Rebar
        - 4 .3 .1 .1.2 Column Form Work
        - 4 .3 .1 .1.3 Column Concreting
      - 4 .3 .1 .2 Shear Wall
        - 4 .3 .1 .2 .1 S'Wall Rebar
        - 4 .3 .1 .2 .2 S'Wall Form Work
        - 4 .3 .1 .2 .3 S'Wall Concreting
      - 4 .3 .1 .3 Slab
        - 4 .3 .1 .3 .1 Slab Form Work
        - 4 .3 .1 .3 .2 Slab Rebar
        - 4 .3 .1 .3 .3 Slab MEP Work
        - 4 .3 .1 .3 .4 Slab Concreting

Location Breakdown Structure	BO1 RESI. BLDG.PROJECT	BO1.1 Ground Floor Level	BO1.1.A Zone A	BO1.2 First Floor Level	BO1.2.A Zone A	BO1.3 Second Floor Level	BO1.3.A Zone A	BO1.3.B Zone B	BO1.4 Third Floor Level	BO1.4.A Zone A	BO1.4.B Zone B
4 CONSTRUCTION											
4 .3 Super Structure											
4 .3 .1 Slab Work											
4 .3 .1 .1 Column											
4 .3 .1 .1.1 Column Rebar		✓		✓		✓	✓		✓	✓	
4 .3 .1 .1.2 Column Form Work		✓		✓		✓	✓		✓	✓	
4 .3 .1 .1.3 Column Concreting		✓		✓		✓	✓		✓	✓	
4 .3 .1 .2 Shear Wall											
4 .3 .1 .2 .1 S'Wall Rebar		✓		✓		✓	✓		✓	✓	
4 .3 .1 .2 .2 S'Wall Form Work		✓		✓		✓	✓		✓	✓	
4 .3 .1 .2 .3 S'Wall Concreting		✓		✓		✓	✓		✓	✓	
4 .3 .1 .3 Slab											
4 .3 .1 .3 .1 Slab Form Work		✓		✓		✓	✓		✓	✓	
4 .3 .1 .3 .2 Slab Rebar		✓		✓		✓	✓		✓	✓	
4 .3 .1 .3 .3 Slab MEP Work		✓		✓		✓	✓		✓	✓	
4 .3 .1 .3 .4 Slab Concreting		✓		✓		✓	✓		✓	✓	

# Location-Work Breakdown Matrix

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
- BO1.4 .3 .1 .A . 1 Column
- **BO1.4 .3 .1 .A . 1.1 Rebar**
- BO1.4 .3 .1 .A . 1.2 Form Work
- BO1.4 .3 .1 .A . 1.3 Concreting
- BO1.4 .3 .1 .A .2 Shear Wall
- BO1.4 .3 .1 .A .2 .1 Rebar
- BO1.4 .3 .1 .A .2 .2 Form Work
- BO1.4 .3 .1 .A .2 .3 Concreting
- BO1.4 .3 .1 .A .3 Slab
- BO1.4 .3 .1 .A .3 .1 Form Work
- BO1.4 .3 .1 .A .3 .2 Rebar
- BO1.4 .3 .1 .A .3 .3 MEP Work
- BO1.4 .3 .1 .A .3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
- BO1.4 .3 .2 .A Slab Work
- BO1.4 .3 .2 .A .1 Column
- **BO1.4 .3 .2 .A .1 .1 Rebar**
- BO1.4 .3 .2 .A .1 .2 Form Work
- BO1.4 .3 .2 .A .1 .3 Concreting
- BO1.4 .3 .2 .A .2 Shear Wall
- BO1.4 .3 .2 .A .2 .1 Rebar
- BO1.4 .3 .2 .A .2 .2 Form Work
- BO1.4 .3 .2 .A .2 .3 Concreting

- BO1.4 .3 .2 .A .3 Slab
- BO1.4 .3 .2 .A .3 .1 Form Work
- **BO1.4 .3 .2 .A .3 .2 Rebar**
- BO1.4 .3 .2 .A .3 .3 MEP Work
- BO1.4 .3 .2 .A .3 .4 Concreting
- BO1.4 .3 .3 Second Floor Level
- BO1.4 .3 .3 .A Slab Work
- BO1.4 .3 .3 .A .1 Column
- **BO1.4 .3 .3 .A .2 Shear Wall**
- BO1.4 .3 .3 .A .3 Slab
- BO1.4 .3 .3 .B Part 2
- BO1.4 .3 .3 .B .1 Column
- **BO1.4 .3 .3 .B .2 Shear Wall**
- BO1.4 .3 .3 .B .3 Slab
- BO1.4 .3 .4 Third Floor Level
- BO1.4 .3 .4 .A Part 1
- **BO1.4 .3 .4 .A .1 Column**
- BO1.4 .3 .4 .A .2 Shear Wall
- BO1.4 .3 .4 .A .3 Slab
- BO1.4 .3 .4 .B Part 2
- BO1.4 .3 .4 .B .1 Column
- **BO1.4 .3 .4 .B .2 Shear Wall**
- BO1.4 .3 .4 .B .3 Slab

## Work-Location Breakdown Matrix

### Work Breakdown Structure

- 4 CONSTRUCTION
- 4 .3 Super Structure
- 4 .3 .1 Slab Work
- 4 .3 .1 .1 Column
  - 4 .3 .1 .1.1 Column Rebar
  - 4 .3 .1 .1.2 Column Form Work
  - 4 .3 .1 .1.3 Column Concreting
- 4 .3 .1 .2 Shear Wall
  - 4 .3 .1 .2 .1 S'Wall Rebar
  - 4 .3 .1 .2 .2 S'Wall Form Work
  - 4 .3 .1 .2 .3 S'Wall Concreting
- 4 .3 .1 .3 Slab
  - 4 .3 .1 .3 .1 Slab Form Work
  - 4 .3 .1 .3 .2 Slab Rebar
  - 4 .3 .1 .3 .3 Slab MEP Work
  - 4 .3 .1 .3 .4 Slab Concreting

Location Breakdown Structure	BO1 RESI. BLDG.PROJECT	BO1.1 Ground Floor Level	BO1.1.A Zone A	BO1.2 First Floor Level	BO1.2.A Zone A	BO1.3 Second Floor Level	BO1.3.A Zone A	BO1.3.B Zone B	BO1.4 Third Floor Level	BO1.4.A Zone A	BO1.4.B Zone B
4 CONSTRUCTION											
4 .3 Super Structure											
4 .3 .1 Slab Work											
4 .3 .1 .1 Column											
4 .3 .1 .1.1 Column Rebar					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .1.2 Column Form Work					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .1.3 Column Concreting					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .2 Shear Wall											
4 .3 .1 .2 .1 S'Wall Rebar					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .2 .2 S'Wall Form Work					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .2 .3 S'Wall Concreting					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .3 Slab											
4 .3 .1 .3 .1 Slab Form Work					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .3 .2 Slab Rebar					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .3 .3 Slab MEP Work					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4 .3 .1 .3 .4 Slab Concreting					<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Task



# Location-Work Breakdown Matrix

- BO1 RESI. BLDG.PROJECT
- ...
- BO1.4 CONSTRUCTION
- ...
- BO1.4 .3 Super Structure
- BO1.4 .3 .1 Ground Floor Level
- BO1.4 .3 .1 .A Slab Work
- BO1.4 .3 .1 .A . 1 Column
- BO1.4 .3 .1 .A . 1.1 Rebar
- BO1.4 .3 .1 .A . 1.2 Form Work
- BO1.4 .3 .1 .A . 1.3 Concreting
- BO1.4 .3 .1 .A . 2 Shear Wall
- BO1.4 .3 .1 .A . 2 .1 Rebar
- BO1.4 .3 .1 .A . 2 .2 Form Work
- BO1.4 .3 .1 .A . 2 .3 Concreting
- BO1.4 .3 .1 .A . 3 Slab
- BO1.4 .3 .1 .A . 3 .1 Form Work
- BO1.4 .3 .1 .A . 3 .2 Rebar
- BO1.4 .3 .1 .A . 3 .3 MEP Work
- BO1.4 .3 .1 .A . 3 .4 Concreting
- BO1.4 .3 .2 First Floor Level
- BO1.4 .3 .2 .A Slab Work
- BO1.4 .3 .2 .A .1 Column
- BO1.4 .3 .2 .A .1 .1 Rebar
- BO1.4 .3 .2 .A .1 .2 Form Work
- BO1.4 .3 .2 .A .1 .3 Concreting
- BO1.4 .3 .2 .A .2 Shear Wall
- BO1.4 .3 .2 .A .2 .1 Rebar
- BO1.4 .3 .2 .A .2 .2 Form Work
- BO1.4 .3 .2 .A .2 .3 Concreting
- BO1.4 .3 .2 .A .3 Slab
- BO1.4 .3 .2 .A .3 .1 Form Work
- BO1.4 .3 .2 .A .3 .2 Rebar
- BO1.4 .3 .2 .A .3 .3 MEP Work
- BO1.4 .3 .2 .A .3 .4 Concreting
- BO1.4 .3 .2 .A .3 Slab
- BO1.4 .3 .2 .A .3 .1 Form Work
- BO1.4 .3 .2 .A .3 .2 Rebar
- BO1.4 .3 .2 .A .3 .3 MEP Work
- BO1.4 .3 .2 .A .3 .4 Concreting
- BO1.4 .3 .3 Second Floor Level
- BO1.4 .3 .3 .A Slab Work
- BO1.4 .3 .3 .A .1 Column
- BO1.4 .3 .3 .A .2 Shear Wall
- BO1.4 .3 .3 .A .3 Slab
- BO1.4 .3 .3 .B Part 2
- BO1.4 .3 .3 .B .1 Column
- BO1.4 .3 .3 .B .2 Shear Wall
- BO1.4 .3 .3 .B .3 Slab
- BO1.4 .3 .4 Third Floor Level
- BO1.4 .3 .4 .A Part 1
- BO1.4 .3 .4 .A .1 Column
- BO1.4 .3 .4 .A .2 Shear Wall
- BO1.4 .3 .4 .A .3 Slab
- BO1.4 .3 .4 .B Part 2
- BO1.4 .3 .4 .B .1 Column
- BO1.4 .3 .4 .B .2 Shear Wall
- BO1.4 .3 .4 .B .3 Slab

## Work-Location Breakdown Matrix

### Work Breakdown Structure

- 4 CONSTRUCTION
- 4 .3 Super Structure
- 4 .3 .1 Slab Work
- 4 .3 .1 .1 Column
  - 4 .3 .1 .1.1 Column Rebar
  - 4 .3 .1 .1.2 Column Form Work
  - 4 .3 .1 .1.3 Column Concreting
- 4 .3 .1 .2 Shear Wall
  - 4 .3 .1 .2 .1 S'Wall Rebar
  - 4 .3 .1 .2 .2 S'Wall Form Work
  - 4 .3 .1 .2 .3 S'Wall Concreting
- 4 .3 .1 .3 Slab
  - 4 .3 .1 .3 .1 Slab Form Work
  - 4 .3 .1 .3 .2 Slab Rebar
  - 4 .3 .1 .3 .3 Slab MEP Work
  - 4 .3 .1 .3 .4 Slab Concreting

Location Breakdown Structure	BO1 RESI. BLDG.PROJECT	BO1.1 Ground Floor Level	BO1.1.A Zone A	BO1.2 First Floor Level	BO1.2.A Zone A	BO1.3 Second Floor Level	BO1.3.A Zone A	BO1.3.B Zone B	BO1.4 Third Floor Level	BO1.4.A Zone A	BO1.4.B Zone B
4 CONSTRUCTION											
4 .3 Super Structure											
4 .3 .1 Slab Work											
4 .3 .1 .1 Column											
4 .3 .1 .1.1 Column Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .1.2 Column Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .1.3 Column Concreting			✓		✓		✓	✓		✓	✓
4 .3 .1 .2 Shear Wall											
4 .3 .1 .2 .1 S'Wall Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .2 .2 S'Wall Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .2 .3 S'Wall Concreting			✓		✓		✓	✓		✓	✓
4 .3 .1 .3 Slab											
4 .3 .1 .3 .1 Slab Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .3 .2 Slab Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .3 .3 Slab MEP Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .3 .4 Slab Concreting			✓		✓		✓	✓		✓	✓

Parade of Trades

# Location-Work Breakdown Matrix

Work-Location Breakdown Matrix

Work Breakdown Structure	Location Breakdown Structure								
	BO1 RESI. BLDG. PROJECT	B01.1 Ground Floor Level	B01.1.A Zone A	B01.2 First Floor Level	B01.2.A Zone A	B01.3 Second Floor Level	B01.3.A Zone A	B01.3.B Zone B	B01.4 Third Floor Level
4 CONSTRUCTION									
4 .3 Super Structure									
4 .3 .1 Slab Work									
4 .3 .1 .1 Column									
4 .3 .1 .1.1 Column Rebar			✓		✓		✓	✓	✓
4 .3 .1 .1.2 Column Form Work			✓		✓		✓	✓	✓
4 .3 .1 .1.3 Column Concreting			✓		✓		✓	✓	✓
4 .3 .1 .2 Shear Wall									
4 .3 .1 .2.1 S'Wall Rebar			✓		✓		✓	✓	✓
4 .3 .1 .2.2 S'Wall Form Work			✓		✓		✓	✓	✓
4 .3 .1 .2.3 S'Wall Concreting			✓		✓		✓	✓	✓
4 .3 .1 .3 Slab									
4 .3 .1 .3.1 Slab Form Work			✓		✓		✓	✓	✓
4 .3 .1 .3.2 Slab Rebar			✓		✓		✓	✓	✓
4 .3 .1 .3.3 Slab MEP Work			✓		✓		✓	✓	✓
4 .3 .1 .3.4 Slab Concreting			✓		✓		✓	✓	✓

- This is actually a representation with work (T) sorted by product breakdown (PBS).
- The matrix makes sorted by either LBS or PBS simple.

# Work Breakdown Matrix

Work-Location Breakdown Matrix

Work Breakdown Structure	Location Breakdown Structure										
	BO1 RESI. BLDG. PROJECT	B01.1 Ground Floor Level	B01.1.A Zone A	B01.2 First Floor Level	B01.2.A Zone A	B01.3 Second Floor Level	B01.3.A Zone A	B01.3.B Zone B	B01.4 Third Floor Level	B01.4.A Zone A	B01.4.B Zone B
4 CONSTRUCTION											
4 .3 Super Structure											
4 .3 .1 Slab Work											
4 .3 .1 .1 Column											
4 .3 .1 .1.1 Column Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .1.2 Column Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .1.3 Column Concreting			✓		✓		✓	✓		✓	✓
4 .3 .1 .2 Shear Wall											
4 .3 .1 .2.1 S'Wall Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .2.2 S'Wall Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .2.3 S'Wall Concreting			✓		✓		✓	✓		✓	✓
4 .3 .1 .3 Slab											
4 .3 .1 .3.1 Slab Form Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .3.2 Slab Rebar			✓		✓		✓	✓		✓	✓
4 .3 .1 .3.3 Slab MEP Work			✓		✓		✓	✓		✓	✓
4 .3 .1 .3.4 Slab Concreting			✓		✓		✓	✓		✓	✓




- Should the axis actually be
  - Product Breakdown (X)
  - Location Breakdown (L)
- And should the matrix be:
  - Work Breakdown Matrix









- Examples: Trimble (4.475B company): Vico Office



- Examples: TopCon (1.56B company): DynaRoad






# Empire State Building: LBMS





- A 102 level building,
  - sketch designs to opening for business in 18 months;
  - achieving (aligned) floor cycles of one floor per day;
  - structure completed in 4.5 months.
- The production was run like an assembly line
  - continuous and aligned production
- Emphasis on controlling the work.
  - First, actual quantities placed in locations were monitored daily.
  - Second, the work crews were checked to ensure they were working in the correct location three times per day.

# Empire State Building: LBMS




- A 102 level building,
  - sketch designs to opening for business in 18 months;
  - achieving (aligned) floor cycles of one floor per day;
  - structure completed in 4.5 months.
- The production was run like an assembly line
  - continuous and aligned production
- Emphasis on controlling the work.
  - First, actual quantities placed in locations were monitored daily.
  - Second, the work crews were checked to ensure they were working in the correct location three times per day.

# Basic Line-of-Balance






# Basic Line-of-Balance




# Integrating CPM/LoB

The relationship between the underlying logic (CPM) and the limits of the lines-of-balance



# Simple Flowline


Calendar



Locations

Tasks






# Case studies



## Some issues that I have encountered while working with VDC

- Planning for structural cycles
- Planning for production efficiency
- Planning for problem solving
- Project monitoring and control
- Defensive scheduling
- Horizontal infrastructure



# Planning for structural cycles


- Planning a structural cycle should not be an accident.
- Location plays a critical role in determining project duration and resource efficiency.
- Here six months removed by changing the Location Breakdown Structure






# Planning for structural cycles

- Removing waiting time by using a smaller cycle area



# Planning for structural cycles

- Splitting a pour but running them apart – why?





# Use 4D with care


- If you cannot see the fit-out inside a complex model
- How do you visualise the complexity of resource management







# Planning for production efficiency

- We don't want to be part of the problem
- Plan for production efficiency



# Planning for problem solving





# Project monitoring and control




- Contractors are displaying very bad practice when controlling projects
  - Poor logic with errors
    - Eg. Dangles, reverse logic
  - No baseline
  - Revising schedule every month
  - Not monitoring progress regularly
  - Poor status reports
  - No forecasting
    - Status is based on whether ahead or behind schedule (so always on schedule!)



Flowline view / Structure  
version 29/6/2012 6:16

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: - - - - - Forecast: . . . . .

Flowline view / Structure  
version 29/6/2012 6:18

GLOBE  
Planner: LBMS


Responsible person:



Flowline view / Structure  
version 29/6/2012 0:20

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: - - - - - Forecast: . . . . .



Flowline view / Structure  
version 29/6/2012 8:21

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: - - - - - Forecast: . . . . .

Flowline view / Structure  
version 29/6/2012 6:23

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: ..... Forecast: - - - - -

History mode  
Schedule Planner v3.2.0.61099

Flowline view / Structure  
version 29/6/2012 8:24

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: - - - - - Forecast: - - - - -



Flowline view / Structure  
version 29/6/2012 6:25

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: ..... Forecast: - - - - -

Flowline view / Structure  
version 29/6/2012 8:26

GLOBE  
Planner: LBMS


Responsible person:



Flowline view / Structure  
version 29/6/2012 0:27

GLOBE  
Planner: LBMS

Responsible person:




Target: ——— Actual: ..... Forecast: - - - - -



Flowline view / Structure  
version 29/6/2012 8:28

GLOBE  
Planner: LBMS

Responsible person:




# Rapid scheduling

- Rapid prototyping



# Horizontal infrastructure



- Alignment based
- Real-world coordi






# Horizontal infrastructure



# Horizontal infrastructure





# Distributed Construction or Maintenance

- Distributed work involves location
- Resources can be managed across locations
- Management by location should be explicit
- Partnering with MPI to create new *Location* functionality for CPM





# Questions?

